Comparative Statement

Nme of Work Providing Fencing, Grill Work & other work to Indira Canteen in Ward No.14,Bagalagunte

Sl.No	Description of work	Unit	Qty	Sanctioned Rate		Manjunath S		Kumar BJ		Sri Baba Construction	
				Rate	Amount	Quated Rate	Amount	Quated Rate	Amount	Quated Rate	Amount
1	2	3	4	5	6	7	8	9	10	11	12
1	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the	Mtr	105.00	868.14	91155.00	860.00	90300.00	900.00	94500.00	920.00	96600.00
2	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two	Sqm	200.00	698.54	139708.00	690.00	138000.00	700.00	140000.00	720.00	144000.00
3	Fabricating, providing and erecting in Position of Security Grill Work. The entire frame work is tobe fixed by means of expansion bolts to the brick pillars with necesarydrilling holes. the work includes providng two coats of enamel painting over one coatr of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using	Sqm	25.00	9692.64	242316.00	9650.00	241250.00	9700.00	242500.00	9720.00	243000.00
4	roviding and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with all leads and lifts	Sqm	172.00	90.72	15604.00	90.00	15480.00	100.00	17200.00	120.00	20640.00
5	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand	Sqm	280.00	31.32	8770.00	30.00	8400.00	50.00	14000.00	70.00	19600.00
	Total Amount				497553.00		493430.00		508200.00		523840.00
	% Percentage						-0.83		2.14		5.28

As per Comparative Statement rate quoted by Class -1 Contractor Sri.Manjunath.S is Rs.493430.00 Which is 0.83% Below for Sanctioned Tender amount Hence the Sri.Manjunath.S quated amount Rs.493430.00 is recommanded for kind approval .

Executive Engineer
Dasarahalli Division
BBMP

Scanned by CamScanner